Switzer Mesa FUTS Improvements
Bid Schedule

Item No.	Description	Qty.	Unit	Unit Price		Total
				In Words	In Figures	
1	Aggregate Trail per CoF 14-01-010.2	1,615	SY			
2	Concrete FUTS Entrance (22 SY)	1	EA			
3	Removable Bollard per CoF 13-03-014	1	EA			
4	18" Ø Culvert + End Sections	45	LF			
5	24" Ø Culvert + End Sections	120	LF			
6	Grade Channel per Detail 7 (190 LF)	1	LS			
7	Grade Channel per Detail 8 (590 LF)	1	LS			
8	Grade Channel per Detail 9 (85 LF)	1	LS			
9	Earth Berm	1	LS			
10	Tree Protection Fence (450 LF)	1	LS			
11	D50 Rip-rap with Filter Fabric - 12" thick	2,600	SF			
12	Check Dam per Detail 4	7	EA			
13	Silt Fence OR Straw Wattle	1,375	LF			
14	Seeding & Landscape Restoration (1.5 Acres)	1	LS			
15	Owner's Allowance	1	EA	Fifteen Thousand Two Hundred Fifty Dollars	15,250.00	15,250.00

Switzer Mesa FUTS Total Bid Amount $ _____

Hospital Rim FUTS Improvements
Bid Schedule

Item No.	Description	Qty.	Unit	Unit Price		Total
				In Words	In Figures	
1	Clear & Grub (Includes Tree Removal)	4,745	SY			
2	Remove & Dispose - Tree > 12"	8	EA			
3	Remove & Dispose - Curb & Gutter	37	LF			
4	Remove & Dispose - Sidewalk	150	SF			
5	Adjust Water Valve	1	EA			
6	Earthwork - Fill Construction (1,345 CY)	1	LS			
7	Subgrade Preparation (6" Scarify)	1,591	SY			
8	Trapezoidal Channel	60	LF			
9	Aggregate Trail per COF 14-01-010.2	1,061	SY			
10	Concrete Trail (5" PCC / 6" ABC)	501	SY			
11	Sidewalk (4" PCC / 3" ABC)	649	SF			
12	Bike Ramp (4" PCC / 3" ABC)	2	EA			
13	MAG 222, Type 'A' Vertical Curb	37	LF			
14	Concrete Scupper (110 SF)	1	EA			
15	18" Ø CMP + End Sections	192	LF			
16	MAG 535, Type 'F' Catch Basin	1	EA			

Hospital Rim FUTS Improvements
Bid Schedule

Item No.	Description	Qty.	Unit	Unit Price		Total
				In Words	In Figures	
17	Signage	1	LS			
18	Rail Fence	320	LF			
19	Seed/Mulch	2,837	SY			
20	Erosion Control Blanket	1,011	SY			
21	Silt Fence	1,513	LF			
22	Straw Wattles	11	EA			
23	Stabilized Construction Entrance	1	LS			
24	As-Built Record Drawings	1	LS			
25	Owner's Allowance	1	LS	Fifteen Thousand Two Hundred Fifty Dollars	15,250.00	15,250.00

Hospital Rim FUTS Total Bid Amount _____ $ _____
In Words *In Figures*

Switzer Mesa FUTS Total Bid Amount _____ $ _____
In Words *In Figures*

Combined Total Bid _____ $ _____
In Words *In Figures*