



Project Number: Wastewater 6

Planning Period: FY '15-'16

Description: Wildcat- Micro Carbon Feed Addition: Project to consist of design for the installation of a new carbon feed system to provide supplemental carbon to optimize denitrification in the anoxic basins at the Wildcat Hill WWTP. The project will include design for a new 5,000 gallon liquid carbon storage tank, two carbon feed pumps, spill containment, electrical and instrumentation, all housed in a new 224 square foot building.

Justification: Project necessary to meet nitrogen levels required by ADEQ permit for reclaimed water and ADEQ Consent Order.

Conceptual Cost:	Project Number:	WW 3320
	Construction Cost:	\$200,000
	Project Cost:	\$200,000

Facility Design:	Project Number:	WW 3320
	Type:	Wastewater Treatment
	Quantity:	

Funding Categories:	Service Area	% Growth/Capacity Fees	% O&M/Rates
	Wildcat Hill WWTP	0%	100%

